

Addendum No. 2

Rock River Water Reclamation District 2019-2020 Sanitary Sewer Lining Capital Project No. 2037 IEPA Project No. L17-5658

This Addendum Number 2, dated May 23, 2019, for the above referenced project, supersedes all contrary and conflicting information in the specifications and contract documents, which are hereby supplemented or revised as follows:

PROJECT SPECIFICATIONS

Section I

1. Bid Schedule, Page 24: The Bid Schedule on page 24 has been revised, eliminating ITEM 220 from the contract (308' of 24" DIA). Bidders shall replace Page 24 issued in Addendum No. 1 with the enclosed. The revised Bid Schedule attached shall be used in submitted bids.


Section II

1. Part 4, Sewer Flow Control: Additional clarification of source of flows provided in Addendum No.1 is provided below:
 - a. Items 30-34, 24" diameter: 1.90 MGD – approximately 90% of flow is in 24" diameter tributary sewer.
 - b. Item 77, 18" diameter: 1.36 MGD - approximately 90% of flow is in 18" diameter tributary sewer.
 - c. Items 216-219, 24" diameter: 4.05 MGD - approximately 75% of flow is discharged via force main into MH 142-034. Max downtime for pump stations discharging to this location is estimated at 2 hours.
 - d. Item 221, 18" diameter: 1.49 MGD - approximately 90% of flow is in 18" diameter tributary sewer.
2. Part 7.1.2 CIPP Structural Requirements, Item 1 (Page 90 of 102): Revise the first sentence of the last paragraph to read: "The finished thickness of cured pipe shall not vary from the nominal thickness specified or required by structural calculations by more than **10%**."
3. Part 8.1.3 Sewer Service Reinstatement, Item 3 (Page 95 of 102): Revise Item 3 to read: "If the Contractor cannot determine through pan and tilt televising methods in the pre-lining video inspection if a service is live or in use, he shall notify the District immediately. The District shall perform the tests necessary to determine if the service is in use and provide instruction to the Contractor in regards to service reinstatement."

This information shall be taken into consideration when preparing your bid. This addendum will be E-mailed to all plan holders as well as posted to the District's website at www.rwrwd.dst.il.us.

End of Addendum No. 2

Issued May 23, 2019
Rock River Water Reclamation District



Christopher T. Baer
Engineering Manager

Encl: Revised Bid Schedule (P.24)

BIDDER agrees to perform all the work described in the CONTRACT DOCUMENTS for the following unit prices or lump sum:

Bid Schedule – REVISED Per Addendum No. 2

NOTE: BIDS shall include sales tax and all other applicable taxes and fees.

No.	Item	Quantity	Unit	Unit Price	Total Price
1	6" Sanitary Sewer Lining	243	LF		
2	8" Sanitary Sewer Lining	36,742	LF		
3	9" Sanitary Sewer Lining	6,020	LF		
4	10" Sanitary Sewer Lining	3,723	LF		
5	12" Sanitary Sewer Lining	7,426	LF		
6	15" Sanitary Sewer Lining	1,363	LF		
7	18" Sanitary Sewer Lining	696	LF		
8	24" Sanitary Sewer Lining	2,281	LF		
9	Service Reinstatement	967	EA		
10	Protruding Service Removal	60	EA		
11	Traffic Control & Protection	1	LS		

TOTAL OF BID..... \$ _____

Bidder is currently certified as an MBE or WBE under EPA’S DBE Program? Yes _____ No _____

Respectfully submitted,

Signature

Mailing Address

Printed Name

City, State Zip

Title

Email Address

Telephone Number

Fax Number

(SEAL – if BID is by a corporation)

Attest