

Addendum No. 1

Rock River Water Reclamation District Manhole Lining 2019-2020 Capital Project No. 2013

This Addendum Number 1, dated August 14, 2019, for the above referenced project, supersedes all contrary and conflicting information in the specifications and contract documents, which are hereby supplemented or revised as follows:

PROJECT SPECIFICATIONS

Section I, Article 3

1. The following products have been added to *Part 2.2 Approved Lining Systems*:
 - a. Sherwin Williams Dura-Plate 6100 Epoxy.
 - b. DuraSeal, LLC DuraLine Epoxy.
 - c. Quadex Structure Guard-QS Epoxy.
 - d. Madewell Mainstay DS-5 High Build Epoxy Coating.
2. The following minimum product requirements listed in *Part 2.2 Approved Lining Systems* have been revised:
 - a. Minimum Tensile Strength (ASTM D638): 5,600 psi.
 - b. Minimum Flexural Strength (ASTM D790): 7,000 psi.

Section II, Contract Forms

1. *Proposal*, Page 1 of 4: Revise the Completion Date to March 30, 2020.
2. *Agreement*, Page 4 of 5: Replace the last sentence of *Part 10, Time* as follows: The completion date for this project shall be March 30th, 2020.

This information shall be taken into consideration when preparing your bid. This addendum will be E-mailed to all plan holders as well as posted to the District's website at www.rwrwd.dst.il.us.

End of Addendum No. 1

Issued August 14, 2019
Rock River Water Reclamation District



Christopher T. Baer
Engineering Manager