

## **Addendum No. 2**

### **Rock River Water Reclamation District Cherry Valley Parallel Force Main Capital Project No. 1420 IEPA Project No. L17-4667**

This Addendum No. 2, dated April 3, 2020, for the above-referenced project, supersedes all contrary and conflicting information in the specifications and contract documents, which are hereby supplemented or revised as follows:

#### **CLARIFICATIONS**

1. Bids may still be delivered to the Rock River Water Reclamation District Administration Building at 3501 Kishwaukee Street, Rockford, IL. A container for receiving bids will be placed inside the foyer at the main entrance of the building. District Engineering personnel will collect the submitted bids at the submittal deadline. The District will provide a link via email to plan holders 48 hours prior to the scheduled bid opening to allow plan holders to view the opening remotely.
2. Additional record information regarding existing 30" diameter Prestressed Concrete Cylinder Pipe (PCCP): The existing 30" PCCP was manufactured by Interpace Corporation (Job No. SB-78-48) with Class III prestressing wire. Destructive testing performed in 2010 indicates Class IV prestressing wire may have been substituted at the time of manufacture. The pipe was installed in 1978.

#### **SECTION I, BIDDING REQUIREMENTS & CONTRACT DOCUMENTS**

1. Replace Part 3.8, Statement of Qualifications in its entirety with the following:
  - a. Each proposal must be accompanied by a Statement of Qualifications certifying that the bidder is registered to do business in the State of Illinois. The proposal must provide documentation that the bidder possesses the appropriate financial, material, equipment, facility and personnel resources and expertise necessary to meet all contractual obligations as described in 3.10.2, Evaluation of Responsibility. The District shall be the sole judge of responsibility and reserves the right to request additional information as needed to evaluate bids prior to making an award.
2. Replace Part 3.10.2.f with the following:
  - a. Have satisfactorily completed three (3) similar contracts within the last five (5) years having a combined total value equal to or greater than \$10,000,000.00.

#### **SECTION II, DETAILED SPECIFICATIONS**

1. Part 15, Combination Air/Vacuum Release Valve and Vault: Vent-Tech model 04SXG16SCS is an approved equivalent to the Vent-o-Mat valve specified. This also applies to the Air Release Valve and Vault Detail shown on Plan Sheet 54 of 80 of the Plans.
2. Part 19, Line Stop, Complete: Valves utilized for tapping the 30" diameter PCCP shall be removed after use. Valves utilized on pipe diameters less than 30" shall be permanent.

## **SECTION VI, PERMITS**

1. IDOT Utility Permit No. 219084 expiration has been extended to September 3, 2020.
2. Winnebago County Permit No. 6019011/U: The Contractor shall resubmit this permit for renewal following award. Permits are only valid for a six (6) month period.

## **PLANS**


1. Sheet 23 of 80: Delete Notes 1 and 2 below "Construction Staging" and replace with the following:
  - a. Contractor shall not cut or remove pavement on Perryville Road or Barley Ridge Trail until the proposed casing pipes under U.S. 20 and Perryville Road are installed and approved by the RRWRD.
  - b. No work or alterations to the existing 30" diameter force main will be allowed until the proposed force main piping is installed, successfully tested and operational.

This information shall be taken into consideration when preparing your bid. This addendum will be Emailed to all plan holders as well as posted to the District's website at [www.rrwrddst.il.us](http://www.rrwrddst.il.us).

**End of Addendum No. 2**

Issued April 3, 2020

**Rock River Water Reclamation District**



Christopher T. Baer, P.E.  
Director of Engineering