

Addendum No. 1

Rock River Water Reclamation District 2020-2021 Sanitary Sewer System Lining Capital Project No. 2137

This Addendum Number 1, dated September 11, 2020, for the above referenced project, supersedes all contrary and conflicting information in the specifications and contract documents, which are hereby supplemented or revised as follows:

PROJECT SPECIFICATIONS

Article 2, Instructions to Bidders

1. Part 3.5 Form, Preparation, and Presentation of Proposals

- Clarification for bidders intending to deliver bids in-person: Due to the ongoing COVID-19 pandemic, the Steve Graceffa Administration Building is closed to the general public. Bids may still be delivered in-person. Bids delivered in-person must be placed in the blue bid box located in the foyer of the main entrance of the Steve Graceffa Administration Building located at 3501 Kishwaukee Street, Rockford, Illinois, 61109, prior to the due date and time. Signage will be in place directing those wishing to attend the public opening to the south entrance of the District Board Room where the opening will be held. Those in attendance must wear a face covering or mask.

Article 3, Detailed Specifications

1. Part 9.3 CIPP Structural Requirements, Cured CIPP Thickness

- Revise the first sentence of the last paragraph as follows: The finished thickness of the cured pipe shall not vary from the nominal minimum thickness specified or required by more than 10%.

2. Part 10, Sewer Service Reinstatement

- Replace Part 10.1.3 with the following: If the Contractor cannot ascertain through pan and tilt televising methods whether a sewer service is live or in use, he shall notify the District seventy-two (72) hours, minimum, in advance of lining the associated main line. The District will provide final direction regarding service reinstatement for services in question.


3. Part 11, Protruding Service Removal

- Replace Part 11.1, General with the following: It shall be the responsibility of the Contractor to clear the line of service connections protruding greater than one inch (1") in length. Protruding service connections shall be ground within one-half inch (1/2") of the main line pipe prior to lining. Protruding services must be removed/ground utilizing a robotic cutting tool; the use of "can" cutters will not be allowed. The District must be notified of each service protruding greater than one inch (1") prior to removal. If inspection reveals the protruding service cannot be removed by conventional cutting equipment, the Contractor shall advise the District to make an open-cut repair to remove the obstruction.

This information shall be taken into consideration when preparing your bid. This addendum will be E-mailed to all plan holders as well as posted to the District's website at www.rwrddst.il.us.

End of Addendum No. 1

Issued September 11, 2020
Rock River Water Reclamation District


Christopher T. Baer
Engineering Manager

Encl: